## San Luis Obispo County

**Department of Public Works & Transportation** 



**2014** Public Improvement Standards

(STANDARD DETAILS ONLY)

Available Online at: http://www.slocounty.ca.gov/PW/DevServ/PublicImprovementStandards.htm

### **Standard Construction Drawings**


Rural Road Standards	۸.4
Rural Road Design Criteria	A-1
Typical Rural Road Section - Multiuse Path	A-1a
Typical Rural Road Section - Gravel Road Standard	A-1b
Typical Rural Road Section - Less than 400 Future ADT	A-1c
Typical Rural Road Section - 401 to 1000 Future ADT	<u>A-1d</u>
Typical Rural Road Section - 1001 to 6000 Future ADT	A-1e
Typical Rural Road Section - Over 6000 Future ADT	A-1f
Typical Rural Road Section - Less than 250 Future ADT	A-1b
Typical Rural Road Section - 250 to 400 Future ADT A-1c	
Typical Rural Road Section - 401 to 1000 Future ADT Flat & Rolling	A-1d
Typical Rural Road Section - 401 to 1000 Future Mountainous	A-1e
Typical Rural Road Section - 1000 to 3000 Future ADT Flat & Rolling	A-1f
Typical Rural Road Section - 1000 to 3000 Future ADT Mountainous	A-19
Typical Rural Road Section - 3001 to 5000 Future ADT	A-1h
— Sloped Edge High Speed Rural Roadways (>40 mph)	A-1i
Typical Rural Road Section - Gravel Road Standard	A-1j
Urban Street Standards	
Urban Street Design Criteria	.A-2
Typical Street Road Section - Multiuse Path	.A-2a
Typical Street Road Section - Less than 500 Future ADT	A-2b
Typical Street Road Section - 500 to 6000 Future ADT	A-2c
Typical Street Road Section - 6001 to 16000 Future ADT	A-2d
Typical Street Road Section - 16001 to 24000 Future ADT	A-2e
Typical Street Road Section – Urban Residential w/o Sidewalks	A-2R
Typical Street Road Section - Less than 500 Future ADT Flat, Rolling & Mountainous	A-2b
Typical Street Road Section - 500 to 5000 Future ADT Flat	
500 to 1500 Future ADT Rolling & Mountainous	A-2c
Typical Street Road Section - 5001 to 16000 Future ADT without Parking	
5001 to 16000 Future ADT with Parking	A-2c
Typical Street Road Section - 16000 to 24000 Future ADT	A-2∈
0	
Commercial-Industrial Road Standards	
Commercial - Industrial Road Design Criteria	A-3
Typical Commercial-Industrial - Rural Roads	
Less Than 5000 Future ADT	A-3a
Typical Commercial-Industrial - Urban Streets	4 01
Less Than 5000 & 5000-16000 Future ADT	A-3b
Typical Commercial-Industrial - Urban Streets Greater Than 16000 Future ADT	A-3c
Dead Deales Outrain	
Road Design Criteria	۸ ،
Stopping Sight Distance on Sag Vertical Curves	A-4
Stopping Sight Distance on Crest Vertical Curves	A-4a
Super-Elevation on Horizontal Curves	A-4b
Sight Distance Design Criteria	
Sight Distance Design Criteria Stopping Sight Distance on Horizontal Curves	A-5
	A-5 A-5a
0'' 5'' 0 1 1	A-58
Site Distance Control Areas	A-3D


Road Layout Criteria	
Rural Cul-de-Sac	A-6
Urban Cul-de-Sac	A-6a
Typical Knuckle	A-6b
Urban Bus Turnout & Loading Area	A-6c
Rural Bus Turnout & Loading Area	A-6c.1
Standard Bulb-Out (Angled Parking on Major Road)	A-6d
Standard Bulb-Out (Parallel Parking on Major Road)	A-6e
Driveways: Rural	
Rural Driveway, Layout Standards	
Rural Residential Driveway, for Edge of Pavement (No Dike)	B-1a
Rural Residential Driveway, for Type "A" HMA Dike	B-1b
Driveways: Rural (continued)	
Rural Residential Driveway, for Type "D" & "E" HMA Dikes	B-1b.1
Rural Residential Driveway, for Edge of Pavement with Culvert	B-1c
Rural Residential Driveway, for Edge of Pavement w/ Retaining Wall	B-1d
Rural Driveway Approach, for use on High Speed and/or High Volume Roadways	B-1e
Driveways: Urban	
Urban Residential Driveway, Layout Standards	B-2
Urban Residential Driveway, Residential Driveway	B-2a
Driveways: Commercial-Industrial	
Commercial-Industrial Driveway, Layout Standards	
Commercial-Industrial Driveway, Standard Driveway	
Commercial-Industrial Driveway, High Volume Driveway	
Commercial-Industrial Driveway, Upward / Downward Driveway	B-3c
Curb, Gutter & Sidewalk	
Expansion & Weakened Plane Joint Requirements	
Type "A" Concrete Curb & Gutter	
Type "C" Concrete Curb	
Hot Mix Asphalt (HMA) Dikes	C-3
Sidewalks	C-4
Curb Ramps	C-5
Hot Mix Asphalt Ramp Detail	C-5a
Drainage	
Deep Retention Basin	D-1
Shallow Retention Basin	D-1a
Catch Basin	D-2
Rural Catch Basin - Edge of Pavement Condition	D-2a
Rural Catch Basin - Hot Mix Asphalt Dike Condition	D-2b
Road Side Infiltrator (RSI)	D 30
Storm Drain Manhole for Pipe Diameters from 18" to 36"	D 3
Storm Drain Manhole for Pipe Diameters Greater Than 36"	
Sidewalk Underdrain, Residential	D 4
Sidewalk Underdrain, Residential Parkway (LID Alternative)	
Sidewalk Underdrain, Commercial (Zero Setback)	D-4b
Cross Gutter & Spandrel	D-5

Hydrology	
Average Annual Rainfall	H-1
Time of Concentration for Watershed Less Than 200 Acres	H-2
Runnoff Coefficients for Developed Areas	H-3
Runnoff Coefficients for Undeveloped Areas	H-3a
Rainfall Intensity Data	H-4
Rock Slope Protection Sizing Method at Culvert Outlets	H-5
Layout	
Standard County Title Blocks	L-1
Standard Abbreviations	L-2

Miscellaneous	
Standard Street Monument for Paved Roads	M-1
Standard Street Monument for Gravel Roads	M-1a
Metal Beam Barricade	M-2
Temporary Wood Beam Barricade	
Sidewalk Barricade	110
Standard Street Sign	N 4 -
Tree Trimming Methods	M-5a
Tree Protection Detail	N 1 CL
Storm Drain Marker	Me
Repair	
Allowable Pavement Seam Locations	R-1
Rural Road Widening	D 0
Urban Street Widening	D 20
Trench Repair, Transverse Trenches and Bore Pits	R-3
Trench Repair, Longitudinal Trenches	R-3a
Curb, Gutter & Sidewalk Repair	D 4
Sanitary Sewer	
Sewer Manhole	S-1
Sewer Drop Manhole	S-1a
Sewer Main Cleanout	C 2
Sewer Lateral	S-3
Sewer Lateral for Deep Mains	
Utilities	
Location of Utilities	U-1
Location of Service Laterals	U-2
Utility Separation Criteria	U-3
Utility Separation Criteria, Case 1: New Sewer Mains	U-3a
Utility Separation Criteria, Case 2: New Water Mains	U-3b
Trench Detail, Paved Surfaces	U-4
Trench Detail, Outside Roadway Prism	U-4a
Shallow Trench Detail	11.41
Water	
Thrust Block Requirements, 1 of 2	W-1
Thrust Block Requirements, 2 of 2	W-1a
Fire Hydrant Detail	W-2
Valve Anchor & Box	W-3
Water Service Connection	W-4
1-1/2" Blow-Off Assembly	W-5
2" Blow-Off Assembly	W-5a
Air and Vacuum Relief Assembly	W-6
Water Sampling Station	W-7
New Waterline Connection Details	W-8
New Waterline Flushing Detail	W-9
Waterline Cut-In Tee & Hot Tap Assembly	W-10

Revisions								
Description	Approved	Date	Description	Approved	Date			
NOTE 7	REM	NOV 07	NOTE 9		MAY 14			
REPLACE AC WITH HMA, NOTE 4	GDM	JAN 11						





#### NOTES:

- 1. THE STRUCTURAL ROAD SECTION SHALL BE DETERMINED AT THE TIME OF CONSTRUCTION BASED ON THE SUBGRADE R-VALUE AND THE TRAFFIC INDEX (TI) AS PROVIDED BY THE DEPARTMENT, AND IN NO CASE SHALL THE ZONE OF COMPACTION BE LESS THAN 2.5-FEET IN THICKNESS. THE ROAD SECTION SHALL BE APPROVED BY THE DEPARTMENT PRIOR TO CONSTRUCTION.
- 2. TYPICAL SECTION SHALL BE:

HOT MIX ASPHALT (HMA) PER THE DESIGN STANDARDS TO 95% RELATIVE COMPACTION, OVER


CLASS II AGGREGATE BASE TO 95% RELATIVE COMPACTION, OVER


222212" MINIMUM SUBGRADE TO 95% RELATIVE COMPACTION

- 3. CUT AND FILL SLOPES SHALL NOT EXCEED 2 HORIZONTAL:1 VERTICAL (OR 3h:1v IN NATIVE SAND) WITHOUT PRIOR APPROVAL BY THE DEPARTMENT.
- 4. HMA DIKE REQUIREMENTS PER C-3.
- 5. THE PROJECT ENGINEER SHALL ACCOMMODATE FOR ROADSIDE DRAINAGE SUCH THAT IT DOES NOT ERODE THE AGGREGATE SHOULDER. THE SIDE SLOPE OF ANY DRAINAGE SWALE DIRECTLY ADJACENT TO THE EDGE OF ROADWAY SHALL NOT EXCEED 4h:1v. DESIGN AND CONSTRUCTION SHALL BE TO THE SATISFACTION OF THE DEPARTMENT.
- 6. THE AGGREGATE BASE MATERIAL SHALL EXTEND TO THE EDGE OF THE FILL SLOPE (CHOKER) TO ALLOW FOR STRUCTURAL ROAD SECTION DRAINAGE.
- ADDITIONAL WIDTH SHALL BE PROVIDED WHERE TURN AND/OR BICYCLE LANES ARE REQUIRED BY THE DESIGN STANDARDS.
- 8. A STRIPING AND SIGNAGE PLAN SHALL BE REQUIRED BY THE DEPARTMENT WHEN BIKE LANES, NO PARKING ZONES, SIGNAGE, AND PAVEMENT MARKINGS ARE A REQUIRED COMPONENT OF THE IMPROVEMENTS.
- 9. UNPAVED SHOULDER WIDTH MAY BE REDUCED BY 2 FEET WITH APPROVAL BY DEPARTMENT.



Revisions								
Description	Approved	Date	Description	Approved	Date			
NOTE 7	REM	NOV 07	NOTE 9		MAY 14			
REPLACE AC WITH HMA, NOTE 4	GDM	JAN 11						






#### NOTES:

- 1. THE STRUCTURAL ROAD SECTION SHALL BE DETERMINED AT THE TIME OF CONSTRUCTION BASED ON THE SUBGRADE R-VALUE AND THE TRAFFIC INDEX (TI) AS PROVIDED BY THE DEPARTMENT, AND IN NO CASE SHALL THE ZONE OF COMPACTION BE LESS THAN 2.5-FEET IN THICKNESS. THE ROAD SECTION SHALL BE APPROVED BY THE DEPARTMENT PRIOR TO CONSTRUCTION.
- 2. TYPICAL SECTION SHALL BE:
  - HOT MIX ASPHALT (HMA) PER THE DESIGN STANDARDS TO 95% RELATIVE COMPACTION, OVER
- CLASS II AGGREGATE BASE TO 95% RELATIVE COMPACTION, OVER
- 12" MINIMUM SUBGRADE TO 95% RELATIVE COMPACTION
- 3. CUT AND FILL SLOPES SHALL NOT EXCEED 2 HORIZONTAL:1 VERTICAL (OR 3h:1v IN NATIVE SAND) WITHOUT PRIOR APPROVAL BY THE DEPARTMENT.
- 4. HMA DIKE REQUIREMENTS PER C-3.
- 5. THE PROJECT ENGINEER SHALL ACCOMMODATE FOR ROADSIDE DRAINAGE SUCH THAT IT DOES NOT ERODE THE AGGREGATE SHOULDER. THE SIDE SLOPE OF ANY DRAINAGE SWALE DIRECTLY ADJACENT TO THE EDGE OF ROADWAY SHALL NOT EXCEED 4h:1v. DESIGN AND CONSTRUCTION SHALL BE TO THE SATISFACTION OF THE DEPARTMENT.
- 6. THE AGGREGATE BASE MATERIAL SHALL EXTEND TO THE EDGE OF THE FILL SLOPE (CHOKER) TO ALLOW FOR STRUCTURAL ROAD SECTION DRAINAGE.
- ADDITIONAL WIDTH SHALL BE PROVIDED WHERE TURN AND/OR BICYCLE LANES ARE REQUIRED BY THE DESIGN STANDARDS.
- 8. A STRIPING AND SIGNAGE PLAN SHALL BE REQUIRED BY THE DEPARTMENT WHEN BIKE LANES, NO PARKING ZONES, SIGNAGE, AND PAVEMENT MARKINGS ARE A REQUIRED COMPONENT OF THE IMPROVEMENTS.
- 9. UNPAVED SHOULDER WIDTH MAY BE REDUCED BY 2 FEET WITH APPROVAL BY THE DEPARTMENT




Scale:	Adopted:
NTS	2011
Drawing No:	100
Sheet No:	

Revisions								
Description	Approved	Date	Description	Approved	Date			
CHANGE 6,000 TO 5,000 FUTURE ADT	REM	NOV 07	CHANGE FUTURE ADT RANGE, NOTE 8, SHLDR DIMS		MAY 14			
REPLACE AC WITH HMA, NOTE 4, 3' MIN. TO HINGE	GDM	JAN 11						



#### I: WHERE HMA DIKE IS NOT REQUIRED

**SHLDR** 



II: WHERE HMA DIKE IS REQUIRED4

#### NOTES

- 1. THE STRUCTURAL ROAD SECTION SHALL BE DETERMINED AT THE TIME OF CONSTRUCTION BASED ON THE SUBGRADE R-VALUE AND THE TRAFFIC INDEX (TI) AS PROVIDED BY THE DEPARTMENT, AND IN NO CASE SHALL THE ZONE OF COMPACTION BE LESS THAN 2.5-FEET IN THICKNESS. THE ROAD SECTION SHALL BE APPROVED BY THE DEPARTMENT PRIOR TO CONSTRUCTION.
- 2. TYPICAL SECTION SHALL BE:

HOT MIX ASPHALT (HMA) PER THE DESIGN STANDARDS TO 95% RELATIVE COMPACTION, OVER

CLASS II AGGREGATE BASE TO 95% RELATIVE COMPACTION, OVER

2////212" MINIMUM SUBGRADE TO 95% RELATIVE COMPACTION

- 3. CUT AND FILL SLOPES SHALL NOT EXCEED 2 HORIZONTAL:1 VERTICAL (OR 3h:1v IN NATIVE SAND) WITHOUT PRIOR APPROVAL BY THE DEPARTMENT.
- 4. HMA DIKE REQUIREMENTS PER C-3.
- 5. THE PROJECT ENGINEER SHALL ACCOMMODATE FOR ROADSIDE DRAINAGE SUCH THAT IT DOES NOT ERODE THE AGGREGATE SHOULDER. THE SIDE SLOPE OF ANY DRAINAGE SWALE DIRECTLY ADJACENT TO THE EDGE OF ROADWAY SHALL NOT EXCEED 4h:1v. DESIGN AND CONSTRUCTION SHALL BE TO THE SATISFACTION OF THE DEPARTMENT.
- 6. THE AGGREGATE BASE MATERIAL SHALL EXTEND TO THE EDGE OF THE FILL SLOPE (CHOKER) TO ALLOW FOR STRUCTURAL ROAD SECTION DRAINAGE.
- A STRIPING AND SIGNAGE PLAN SHALL BE REQUIRED BY THE DEPARTMENT WHEN BIKE LANES, NO PARKING ZONES, SIGNAGE, AND PAVEMENT MARKINGS ARE A REQUIRED COMPONENT OF THE IMPROVEMENTS.
- 8. UNPAVED SHOULDER WIDTH MAY BE REDUCED BY 2 FEET WITH APPROVAL BY DEPARTMENT


# DEPARTMENT OF PUBLIC WORKS & TRANSPORTATION TYPICAL RURAL ROAD SECTION 1001 TO 6000 FUTURE ADT

Scale: Adopted: 2011


Drawing No: A-1 600

Sheet No: 1 OF 1

Revisions								
Description	Approved	Date	Description	Approved	Date			
CHANGE 6,000 TO 5,000 FUTURE ADT	REM	NOV 07	ADT RANGE, NOTE 8		MAY 14			
REPLACE AC WITH HMA, NOTE 4, 3' MIN. TO HINGE	GDM	JAN 11						



#### I: WHERE HMA DIKE IS NOT REQUIRED



## II: WHERE HMA DIKE IS REQUIRED4


#### NOTES:

- 1. THE STRUCTURAL ROAD SECTION SHALL BE DETERMINED AT THE TIME OF CONSTRUCTION BASED ON THE SUBGRADE R-VALUE AND THE TRAFFIC INDEX (TI) AS PROVIDED BY THE DEPARTMENT, AND IN NO CASE SHALL THE ZONE OF COMPACTION BE LESS THAN 2.5-FEET IN THICKNESS. THE ROAD SECTION SHALL BE APPROVED BY THE DEPARTMENT PRIOR TO CONSTRUCTION.
- 2. TYPICAL SECTION SHALL BE:
- HOT MIX ASPHALT (HMA) PER THE DESIGN STANDARDS TO 95% RELATIVE COMPACTION, OVER CLASS II AGGREGATE BASE TO 95% RELATIVE COMPACTION, OVER


2////212" MINIMUM SUBGRADE TO 95% RELATIVE COMPACTION

- 3. CUT AND FILL SLOPES SHALL NOT EXCEED 2 HORIZONTAL:1 VERTICAL (OR 3h:1v IN NATIVE SAND) WITHOUT PRIOR APPROVAL BY THE DEPARTMENT.
- 4. HMA DIKE REQUIREMENTS PER C-3.
- 5. THE PROJECT ENGINEER SHALL ACCOMMODATE FOR ROADSIDE DRAINAGE SUCH THAT IT DOES NOT ERODE THE AGGREGATE SHOULDER. THE SIDE SLOPE OF ANY DRAINAGE SWALE DIRECTLY ADJACENT TO THE EDGE OF ROADWAY SHALL NOT EXCEED 4h:1v. DESIGN AND CONSTRUCTION SHALL BE TO THE SATISFACTION OF THE DEPARTMENT.
- 6. THE AGGREGATE BASE MATERIAL SHALL EXTEND TO THE EDGE OF THE FILL SLOPE (CHOKER) TO ALLOW FOR STRUCTURAL ROAD SECTION DRAINAGE.
- 7. A STRIPING AND SIGNAGE PLAN SHALL BE REQUIRED BY THE DEPARTMENT WHEN BIKE LANES, NO PARKING ZONES, SIGNAGE, AND PAVEMENT MARKINGS ARE A REQUIRED COMPONENT OF THE IMPROVEMENTS.
- 8. UNPAVED SHOULDER WIDTH MAY BE REDUCED BY 2 FEET WITH APPROVAL BY DEPARTMENT


# DEPARTMENT OF PUBLIC WORKS & TRANSPORTATION TYPICAL RURAL ROAD SECTION OVER 6000 FUTURE ADT



Revisions								
Description	Approved	Date	Description	Approved	Date			
NOTE 5	REM	NOV 07	FUTURE ADT		MAY 14			
REPLACE AC WITH HMA	GDM	JAN 11						



#### I: LESS THAN 500 FUTURE ADT-FLAT & ROLLING



#### II: LESS THAN 500 FUTURE ADT-MOUNTAINOUS

#### NOTES:

- 1. THE STRUCTURAL ROAD SECTION SHALL BE DETERMINED AT THE TIME OF CONSTRUCTION BASED ON THE SUBGRADE R-VALUE AND THE TRAFFIC INDEX (TI) AS PROVIDED BY THE DEPARTMENT, AND IN NO CASE SHALL THE ZONE OF COMPACTION BE LESS THAN 2.5-FEET IN THICKNESS. THE ROAD SECTION SHALL BE APPROVED BY THE DEPARTMENT PRIOR TO CONSTRUCTION.
- 2. TYPICAL SECTION SHALL BE:
  - HOT MIX ASPHALT (HMA) PER THE DESIGN STANDARDS TO 95% RELATIVE COMPACTION, OVER CLASS II AGGREGATE BASE TO 95% RELATIVE COMPACTION, OVER


2////2 12" MINIMUM SUBGRADE TO 95% RELATIVE COMPACTION

SUBGRADE AND AGGREGATE BASE COMPACTION REQUIREMENTS SHALL EXTEND TO THE BACK OF CURB OR TO THE BACK OF ATTACHED SIDEWALK (WHICHEVER CONDITION IS APPLICABLE).


- 3. CUT AND FILL SLOPES SHALL NOT EXCEED 2 HORIZONTAL:1 VERTÍCAL (OR 3h:1v IN NATIVE SAND) WITHOUT PRIOR APPROVAL BY THE DEPARTMENT.
- 4. ATTACHED OR DETACHED SIDEWALK TYPE AND WIDTH PER STANDARD DRAWING C-4 OR AS REQUIRED BY THE PROJECT CONDITIONS OF APPROVAL OR AREA SPECIFIC PLAN.
- ADDITIONAL WIDTH SHALL BE PROVIDED WHERE TURN AND/OR BICYCLE LANES ARE REQUIRED BY THE DESIGN STANDARDS.
- 6. OTHER FACILITIES SUCH AS LANDSCAPING, TRANSIT STOP FACILITIES, PEDESTRIAN, EQUESTRIAN, AND BICYCLE FACILITIES MAY BE REQUIRED BY THE DESIGN STANDARDS.
- 7. LANDSCAPE, IRRIGATION, AND MAINTENANCE OF MEDIANS AND PARKWAYS SHALL BE ADDRESSED IN THE APPROVED PROJECT PLANS. A LOCAL FUNDING SOURCE MUST BE IDENTIFIED.
- 8. WHERE APPLICABLE, ALL IMPROVEMENTS SHALL BE CONSISTENT WITH THE RESPECTIVE COMMUNITY DESIGN PLAN AS ADOPTED BY THE BOARD OF SUPERVISORS.
- 9. A STRIPING AND SIGNAGE PLAN SHALL BE REQUIRED BY THE DEPARTMENT WHEN BIKE LANES, NO PARKING ZONES, SIGNAGE, AND PAVEMENT MARKINGS ARE A REQUIRED COMPONENT OF THE IMPROVEMENTS.



Revisions								
Description	Approved	Date	Description	Approved	Date			
NOTE 5	REM	NOV 07	FUTURE ADT		MAY 14			
REPLACE AC WITH HMA	GDM	JAN 11						



#### I: 500 TO 6000 FUTURE ADT-FLAT



#### II: 500 TO 1500 FUTURE ADT-ROLLING & MOUNTAINOUS

#### NOTES:

- 1. THE STRUCTURAL ROAD SECTION SHALL BE DETERMINED AT THE TIME OF CONSTRUCTION BASED ON THE SUBGRADE R-VALUE AND THE TRAFFIC INDEX (TI) AS PROVIDED BY THE DEPARTMENT, AND IN NO CASE SHALL THE ZONE OF COMPACTION BE LESS THAN 2.5-FEET IN THICKNESS. THE ROAD SECTION SHALL BE APPROVED BY THE DEPARTMENT PRIOR TO CONSTRUCTION.
- 2. TYPICAL SECTION SHALL BE:
  - HOT MIX ASPHALT (HMA) PER THE DESIGN STANDARDS TO 95% RELATIVE COMPACTION, OVER
- CLASS II AGGREGATE BASE TO 95% RELATIVE COMPACTION, OVER
- 12" MINIMUM SUBGRADE TO 95% RELATIVE COMPACTION
  - SUBGRADE AND AGGREGATE BASE COMPACTION REQUIREMENTS SHALL EXTEND TO THE BACK OF CURB OR TO THE BACK OF ATTACHED SIDEWALK (WHICHEVER CONDITION IS APPLICABLE).
- CUT AND FILL SLOPES SHALL NOT EXCEED 2 HORIZONTAL:1 VERTICAL (OR 3h:1v IN NATIVE SAND) WITHOUT PRIOR APPROVAL BY THE DEPARTMENT.
- 4. ATTACHED OR DETACHED SIDEWALK TYPE AND WIDTH PER STANDARD DRAWING C-4 OR AS REQUIRED BY THE PROJECT CONDITIONS OF APPROVAL OR AREA SPECIFIC PLAN.
- 5. ADDITIONAL WIDTH SHALL BE PROVIDED WHERE TURN AND/OR BICYCLE LANES ARE REQUIRED BY THE DESIGN STANDARDS.
- 6. OTHER FACILITIES SUCH AS LANDSCAPING, TRANSIT STOP FACILITIES, PEDESTRIAN, EQUESTRIAN, AND BICYCLE FACILITIES MAY BE REQUIRED BY THE DESIGN STANDARDS.
- 7. LANDSCAPE, IRRIGATION, AND MAINTENANCE OF MEDIANS AND PARKWAYS SHALL BE ADDRESSED IN THE APPROVED PROJECT PLANS. A LOCAL FUNDING SOURCE MUST BE IDENTIFIED.
- 8. WHERE APPLICABLE, ALL IMPROVEMENTS SHALL BE CONSISTENT WITH THE RESPECTIVE COMMUNITY DESIGN PLAN AS ADOPTED BY THE BOARD OF SUPERVISORS.
- A STRIPING AND SIGNAGE PLAN SHALL BE REQUIRED BY THE DEPARTMENT WHEN BIKE LANES, NO PARKING ZONES, SIGNAGE, AND PAVEMENT MARKINGS ARE A REQUIRED COMPONENT OF THE IMPROVEMENTS.




Scale: Adopted: 2011


Drawing No: A-2 600

Sheet No: 1 OF 1

## Revisions Description Approved Date Description Approved Date REPLACE AC WITH HMA, NOTE 3 GDM JAN 11 Image: Company of the province of the



#### I: 6001 TO 16000 FUTURE ADT WITHOUT PARKING



#### II: 6001 TO 16000 FUTURE ADT WITH PARKING

#### NOTES:

- 1. THE STRUCTURAL ROAD SECTION SHALL BE DETERMINED AT THE TIME OF CONSTRUCTION BASED ON THE SUBGRADE R-VALUE AND THE TRAFFIC INDEX (TI) AS PROVIDED BY THE DEPARTMENT, AND IN NO CASE SHALL THE ZONE OF COMPACTION BE LESS THAN 2.5-FEET IN THICKNESS. THE ROAD SECTION SHALL BE APPROVED BY THE DEPARTMENT PRIOR TO CONSTRUCTION.
- 2. TYPICAL SECTION SHALL BE:
  - HOT MIX ASPHALT (HMA) PER THE DESIGN STANDARDS TO 95% RELATIVE COMPACTION, OVER
- CLASS II AGGREGATE BASE TO 95% RELATIVE COMPACTION, OVER
- 12" MINIMUM SUBGRADE TO 95% RELATIVE COMPACTION
  - SUBGRADE AND AGGREGATE BASE COMPACTION REQUIREMENTS SHALL EXTEND TO THE BACK OF CURB OR TO THE BACK OF ATTACHED SIDEWALK (WHICHEVER CONDITION IS APPLICABLE).
- CUT AND FILL SLOPES SHALL NOT EXCEED 4 HORIZONTAL:1 VERTICAL WITHIN THE PUBLIC ROW WITHOUT PRIOR APPROVAL BY THE DEPARTMENT.
- 4. ATTACHED OR DETACHED SIDEWALK TYPE AND WIDTH PER STANDARD DRAWING C-4 OR AS REQUIRED BY THE PROJECT CONDITIONS OF APPROVAL OR AREA SPECIFIC PLAN.
- 5. OTHER FACILITIES SUCH AS LANDSCAPING, TRANSIT STOP FACILITIES, PEDESTRIAN, EQUESTRIAN, AND BICYCLE FACILITIES MAY BE REQUIRED BY THE DESIGN STANDARDS.
- 6. LANDSCAPE, IRRIGATION, AND MAINTENANCE OF MEDIANS AND PARKWAYS SHALL BE ADDRESSED IN THE APPROVED PROJECT PLANS. A LOCAL FUNDING SOURCE MUST BE IDENTIFIED.
- 7. WHERE APPLICABLE, ALL IMPROVEMENTS SHALL BE CONSISTENT WITH THE RESPECTIVE COMMUNITY DESIGN PLAN AS ADOPTED BY THE BOARD OF SUPERVISORS.
- 8. A STRIPING AND SIGNAGE PLAN SHALL BE REQUIRED BY THE DEPARTMENT WHEN BIKE LANES, NO PARKING ZONES, SIGNAGE, AND PAVEMENT MARKINGS ARE A REQUIRED COMPONENT OF THE IMPROVEMENTS.




Scale: Adopted: 2011

Drawing No: A-2 1600

Sheet No: 1 OF 1

Revisions								
Description	Approved	Date	Description	Approved	Date			
REPLACE AC WITH HMA, NOTE 3	GDM	JAN 11						
DRAWING NUMBER		MAY 14						



#### 16,000 TO 24,000 FUTURE ADT

#### NOTES:

- 1. THE STRUCTURAL ROAD SECTION SHALL BE DETERMINED AT THE TIME OF CONSTRUCTION BASED ON THE SUBGRADE R-VALUE AND THE TRAFFIC INDEX (TI) AS PROVIDED BY THE DEPARTMENT, AND IN NO CASE SHALL THE ZONE OF COMPACTION BE LESS THAN 2.5-FEET IN THICKNESS. THE ROAD SECTION SHALL BE APPROVED BY THE DEPARTMENT PRIOR TO CONSTRUCTION.
- 2. TYPICAL SECTION SHALL BE:

 $\blacksquare$  HOT MIX ASPHALT (HMA) PER THE DESIGN STANDARDS TO 95% RELATIVE COMPACTION, OVER

☑ CLASS II AGGREGATE BASE TO 95% RELATIVE COMPACTION, OVER

12" MINIMUM SUBGRADE TO 95% RELATIVE COMPACTION

SUBGRADE AND AGGREGATE BASE COMPACTION REQUIREMENTS SHALL EXTEND TO THE BACK OF CURB OR TO THE BACK OF ATTACHED SIDEWALK (WHICHEVER CONDITION IS APPLICABLE).


- CUT AND FILL SLOPES SHALL NOT EXCEED 4 HORIZONTAL: 1 VERTICAL WITHIN THE PUBLIC ROW WITHOUT PRIOR APPROVAL BY THE DEPARTMENT.
- 4. ATTACHED OR DETACHED SIDEWALK TYPE AND WIDTH PER STANDARD DRAWING C-4 OR AS REQUIRED BY THE PROJECT CONDITIONS OF APPROVAL OR AREA SPECIFIC PLAN.
- 5. WHEN STREET PARKING IS REQUIRED A MINIMUM WIDTH OF 8-FEET SHALL BE PROVIDED.
- 6. OTHER FACILITIES SUCH AS LANDSCAPING, TRANSIT STOP FACILITIES, PEDESTRIAN, EQUESTRIAN, AND BICYCLE FACILITIES MAY BE REQUIRED BY THE DESIGN STANDARDS.
- LANDSCAPE, IRRIGATION, AND MAINTENANCE OF MEDIANS AND PARKWAYS SHALL BE ADDRESSED IN THE APPROVED PROJECT PLANS. A LOCAL FUNDING SOURCE MUST BE IDENTIFIED.
- 8. WHERE APPLICABLE, ALL IMPROVEMENTS SHALL BE CONSISTENT WITH THE RESPECTIVE COMMUNITY DESIGN PLAN AS ADOPTED BY THE BOARD OF SUPERVISORS.
- A STRIPING AND SIGNAGE PLAN SHALL BE REQUIRED BY THE DEPARTMENT WHEN BIKE LANES, NO PARKING ZONES, SIGNAGE, AND PAVEMENT MARKINGS ARE A REQUIRED COMPONENT OF THE IMPROVEMENTS.



Scale: Adopted: 2011
Drawing No: Adopted: Adopte

A-2 2400 Sheet No: 1 OF 1

Revisions					
Description	Approved	Date	Description	Approved	Date
NOTE 7	REM	NOV 07	NOTES 3-10, FIGURE		MAY 14
REPLACE AC WITH HMA, NOTE 4	GDM	JAN 11			



#### NOTES:

- 1. THE STRUCTURAL ROAD SECTION SHALL BE DETERMINED AT THE TIME OF CONSTRUCTION BASED ON THE SUBGRADE R-VALUE AND THE TRAFFIC INDEX (TI) AS PROVIDED BY THE DEPARTMENT, AND IN NO CASE SHALL THE ZONE OF COMPACTION BE LESS THAN 2.5-FEET IN THICKNESS. THE ROAD SECTION SHALL BE APPROVED BY THE DEPARTMENT PRIOR TO CONSTRUCTION.
- 2. TYPICAL SECTION SHALL BE:
  - HOT MIX ASPHALT (HMA) PER THE DESIGN STANDARDS TO 95% RELATIVE COMPACTION, OVER
  - CLASS II AGGREGATE BASE TO 95% RELATIVE COMPACTION, OVER
  - 22 12" MINIMUM SUBGRADE TO 95% RELATIVE COMPACTION
  - SUBGRADE AND AGGREGATE BASE COMPACTION REQUIREMENTS SHALL EXTEND TO THE BACK OF CURB OR TO THE BACK OF ATTACHED SIDEWALK (WHICHEVER CONDITION IS APPLICABLE).
- 3. CUT AND FILL SLOPES SHALL NOT EXCEED 5 HORIZONTAL:1 VERTICAL (OR 3h:1v IN NATIVE SAND) WITHOUT PRIOR APPROVAL BY THE DEPARTMENT.
- 4. TRAVELED LANE WIDTH MAY BE INCREASED TO 12' ON ROAD SEGMENTS CLASSIFIED AS A COLLECTOR OR AS A CLASS III BIKE ROLLE
- 5. ADDITIONAL WIDTH SHALL BE PROVIDED WHERE TURN AND/OR BICYCLE LANES ARE REQUIRED BY THE DESIGN STANDARDS.
- 6. OTHER FACILITIES SUCH AS LANDSCAPING, TRANSIT STOP FACILITIES, PEDESTRIAN, EQUESTRIAN, AND BICYCLE FACILITIES MAY BE REQUIRED BY THE DESIGN STANDARDS.
- 7. LANDSCAPE, IRRIGATION, AND MAINTENANCE OF MEDIANS AND PARKWAYS SHALL BE ADDRESSED IN THE APPROVED PROJECT PLANS. A LOCAL FUNDING SOURCE MUST BE IDENTIFIED.
- 8. WHERE APPLICABLE, ALL IMPROVEMENTS SHALL BE CONSISTENT WITH THE RESPECTIVE COMMUNITY DESIGN PLAN AS ADOPTED BY THE BOARD OF SUPERVISORS.
- 9. A STRIPING AND SIGNAGE PLAN SHALL BE REQUIRED BY THE DEPARTMENT WHEN BIKE LANES, NO PARKING ZONES, SIGNAGE, AND PAVEMENT MARKINGS ARE A REQUIRED COMPONENT OF THE IMPROVEMENTS.
- 10. ALTERNATIVE: PARKING LANE MAY BE SURFACED WITH TURF OR LANDSCAPE PAVERS WHERE PRIVATE MAINTENANCE SOURCE IS APPROVED BY DEPARTMENT.

DEPARTMENT OF PUBLIC WORKS & TRANSPORTATION
TYPICAL URBAN STREET SECTION FOR
RESIDENTIAL AREAS WITHOUT SIDEWALKS
1001 TO 3000 FUTURE ADT-FLAT & ROLLING

Scale: A

Adopted: 2011

Drawing No.

^ A-2R

Sheet No: 1 OF 1